

**ADDENDUM III**

THIWASCO seeks to amend the following in **THIWASCO/046/ UTPRP /2022-2023**; to clarify addendums nos I and II

<b>SN NO</b>	<b>DESCRIPTION</b>	<b>AMENDMENTS</b>		
1	Bill no 4 lot 3.	To be deleted and not Bill 3 lot 3 as in addendum no.1		
2	All pipes & pipe fittings be steel	All pipes and fittings to be either made of Steel spiral welded, Epoxy paint coated and lined, or ductile iron		
3	Bill no.3 lot 3 works: The quantities on these items have been revised as below			
<b>Bill no.</b>	<b>Description</b>	<b>unit</b>	<b>Old quantity</b>	<b>Revised quantities</b>
3.3G.1	Break up and remove all spalling concrete up to depth of 50mm.....	M <sup>2</sup>	912	100
3.3G.2	All plaster repair mortar are to be applied strictly in accordance with the "Master Emaco S 488".....	M <sup>2</sup>	1824	150
3.4G.1	Break up and remove all spalling concrete up to depth of 50mm the damaged perimeter.....	M <sup>2</sup>	352	50
3.4G.2	All plaster repair mortar are to be applied strictly in accordance with the "Master Emaco S 488".....	M <sup>2</sup>	704	50